

DEVELOPER MANUAL: WATER MAIN DESIGN AND CONSTRUCTION STANDARDS

TOWN OF CHANDLER, INDIANA

Adopted: May _____, 2017

Tonya Wester, President

Cheryl Amos, Member

Andrea Johnson, Member

Sean Johnson, Member

Ron Whitledge, Member

Brian Pace, Clerk-Treasurer



May 2017

112-0057-0GS-16DW



TABLE OF CONTENTS

| | | |
|----------|---|-----------|
| 1 | Abbreviations and Definitions | 1 |
| 1.1 | <i>Abbreviations and Definitions</i> | 1 |
| 1.1.1 | Abbreviations | 1 |
| 1.1.2 | Definitions | 1 |
| 2 | The Development Review Process for Water Main Construction | 7 |
| 2.1 | <i>Goals and Objectives</i> | 7 |
| 2.2 | <i>General</i> | 7 |
| 2.3 | <i>Development Review Process Description</i> | 8 |
| 2.3.1 | Preliminary Design Package, Technical Review, and Comments | 10 |
| 2.3.2 | Final Design Package, Technical Review, and Final Plan Approval | 10 |
| 2.3.3 | State and Federal Permits | 10 |
| 2.3.4 | Posting of Bond | 10 |
| 2.3.5 | Pre-Construction Coordination | 11 |
| 2.3.6 | Construction Inspection and Observation | 11 |
| 2.3.7 | Project Acceptance and Dedication | 11 |
| 3 | Standard Development Review Forms | 13 |
| 3.1 | <i>Development Procedures for Water Main Construction Checklist</i> | 13 |
| 3.2 | <i>Chandler Utilities Plan and Specification Review Checklist</i> | 16 |
| 3.3 | <i>Application for Water Main Construction</i> | 19 |
| 3.4 | <i>Substantial Completion Field Inspection Checklist</i> | 23 |
| 3.5 | <i>Letter of Substantial Completion</i> | 25 |
| 3.6 | <i>Letter of Final Acceptance</i> | 28 |
| 3.7 | <i>Water and Sewer Utility Easement</i> | 30 |
| 4 | Water Distribution Facility Design Standards | 35 |
| 4.1 | <i>General Requirements</i> | 35 |
| 4.1.1 | Specifications | 35 |
| 4.1.2 | Permits | 35 |
| 4.1.3 | Drafting Standards | 35 |
| 4.2 | <i>Water Mains</i> | 36 |

| | | |
|----------|---|-----------|
| 4.2.1 | General Configuration | 36 |
| 4.2.2 | Cul-de-sac Water Mains | 36 |
| 4.2.3 | Dead-end Water Mains | 36 |
| 4.2.4 | Easements | 36 |
| 4.2.5 | Separation of Water Mains and Sewers | 37 |
| 4.2.6 | Design Flows & Pressures | 37 |
| 4.2.7 | Special Crossings | 38 |
| 4.2.8 | Valves | 38 |
| 4.2.9 | Fire Hydrants | 39 |
| 4.3 | Water Service Lines | 39 |
| 4.3.1 | General Configuration | 39 |
| 4.3.2 | Design Flows and Pressures | 39 |
| 4.3.3 | Valves | 39 |
| 4.3.4 | Meters | 40 |
| 4.3.5 | Backflow Prevention | 40 |
| 5 | Materials Standards for Water Mains | 41 |
| 5.1 | General | 41 |
| 5.1.1 | Water Mains | 41 |
| 5.1.2 | Water Main Fittings | 41 |
| 5.1.3 | Water Services | 41 |
| 5.1.4 | Valves | 42 |
| 5.1.4.1 | Gate Valves | 42 |
| 5.1.4.2 | Air/Vacuum Release Valves | 42 |
| 5.1.4.3 | Corporation Stops and Curb Stops | 42 |
| 5.1.5 | Appurtenances | 43 |
| 5.1.5.1 | Hydrants | 43 |
| 5.1.5.2 | Tracer Wire | 43 |
| 5.1.5.3 | Valve Boxes / Meter Boxes | 43 |
| 5.1.5.4 | Valve Vaults | 43 |
| 6 | Installation and Construction of Water Mains | 44 |
| 6.1 | General | 44 |

| | | |
|---------|---|----|
| 6.1.1 | Safety | 44 |
| 6.1.2 | Excavation | 44 |
| 6.1.2.1 | Dewatering and Control of Surface Water | 44 |
| 6.1.2.2 | Site Preparation | 44 |
| 6.1.2.3 | Excavating | 45 |
| 6.1.2.4 | Trenching | 45 |
| 6.1.3 | Bedding and Backfill | 46 |
| 6.1.3.1 | General | 46 |
| 6.1.3.2 | Bedding and Backfill Materials | 46 |
| 6.1.3.3 | Backfill of Trench Excavations for Pipes and Conduits | 46 |
| 6.1.3.4 | Bedding | 46 |
| 6.1.3.5 | Backfill Around Pipe | 46 |
| 6.1.4 | Installation of Water Mains | 47 |
| 6.1.4.1 | General | 47 |
| 6.1.4.2 | Installation of Water Mains | 47 |
| 6.1.4.3 | Installation of Valves, Valve Boxes, and Structures | 48 |
| 6.1.5 | Erosion Control | 48 |
| 6.1.5.1 | General | 48 |

FIGURES

| | |
|---|---|
| Figure 1 - 1: Development Review Flow Chart | 9 |
|---|---|

APPENDICES

| | |
|------------------------------|---|
| Appendix A: Standard Details | A |
|------------------------------|---|

1 ABBREVIATIONS AND DEFINITIONS

1.1 ABBREVIATIONS AND DEFINITIONS

For the purposes of this manual, Abbreviations and Definitions shall be interpreted as outlined in this section.

1.1.1 Abbreviations

| | |
|-------|--|
| AHJ | Authority Having Jurisdiction |
| ANSI | American National Standards Institute |
| ASTM | American Society for Testing and Materials |
| AWWA | American Water Works Association |
| FM | Associated Factory Mutual Laboratories |
| IDEM | Indiana Department of Environmental Management |
| IDNR | Indiana Department of Natural Resources |
| INDOT | Indiana Department of Transportation |
| NFPA | National Fire Protection Association |
| OSHA | Occupational Safety and Health Act of 1970 |
| SPECS | Specifications |
| UL | Underwriter's Laboratories, Inc. |

1.1.2 Definitions

Acceptance: The formal written acceptance by the Town of Chandler (Town) of an entire project which has been completed in all respects in accordance with the approved Plans, Specifications, and these Standards including any previously approved modifications thereof.

Adequate Public Facilities: Facilities determined to be capable of supporting and servicing the physical area and designated intensity of the proposed subdivision as determined by the Town Council based upon specific levels of service.

Backfill: Earth and/or other material used to replace material removed from trenches during construction which is above the pipe bedding.

Bedding: That portion of the trench backfill which encases the sewer or water pipe to a minimum depth above and below the bell/barrel of the pipe for the purpose of properly supporting the pipe.

Blowoff Assembly: An apparatus consisting of a gate valve and restrained section of pipe (same size as the main) brought to the surface and installed at a water main terminus or low point in the line to facilitate line draining and to allow the removal of sediments which accumulate in low areas of the pipeline. Design engineers are encouraged to avoid blowoffs by utilizing fire hydrants.

Building Sewer (lateral): The conduit for transporting waste discharged from the building to the public sewer. The sewer later is considered to be privately owned beginning at the wye or tee fitting at the connection to the public sewer main.

Contractor: Any Contractor who meets the Town's requirements and is licensed to enter into contracts for and to perform the work of installing potable water facilities and appurtenances.

Construction Plan: The maps or drawings accompanying a subdivision plat, commercial development, or other use showing the specific location and design of improvements to be installed in accordance with the requirements of the Town Council as a condition of the approval of the plat. The construction plans are typically signed and sealed engineering drawings and are included in the contract documents.

County: The County of Warrick, State of Indiana

Culvert: A closed conduit used for the passage of surface drainage water under a roadway, railroad, canal or other impediment.

Design Criteria: Standards that set specific improvement requirements.

Drainage: Surface water runoff and the removal of water from land by drains, grading or other means during and after construction or development.

Easement: Easements are areas along the line of all public sanitary sewers, storm sewers, and water lines which are outside of dedicated utility or road easements or rights-of-way, and are recorded and dedicated to the Town granting rights along the water line. Easements shall be exclusively for the new water lines. No other easements shall be constructed or encroach upon the easement except with the expressed written approval of the Town.

Elevation: A vertical distance above or below a fixed reference level, usually mean sea level. Typically, elevation is reported in feet using the North American Vertical Datum of 1988 (NAVD 88).

Erosion: The detachment and movement of soil, sediment or rock fragments usually by water, wind, ice or gravity.

Excavation: Removal by any means whatsoever of soil, rock, minerals, mineral substances or organic substances other than vegetation, from water or land on or beneath the land surface thereof, whether exposed or submerged.

Existing Grade or Elevation: The vertical location of the ground surface prior to excavating, filling, and other construction operations.

Final Completion: The time at which the Work (or a specified part thereof) has progressed to the point where, in the opinion of the Engineer or the Town, the Work (or a specified part thereof) is fully completed, in accordance with the project plans and specifications, all punch list and inspection items have been

addressed, surface restoration is complete, and temporary erosion control devices have been removed so that the Town may release final payment, performance bonds, or other securities that remain.

Grade: The average level of the finished surface of the ground adjacent to a referenced structure or facility (may also refer to the slope of a roadway along the centerline).

Haunching: The area in the trench from the bottom to the spring line of the pipe.

Horizontal Directional Drilling (HDD): Trenchless construction method for installing water main pipe and service lines.

INDOT SS: Indiana Department of Transportation Standard Specifications, and applicable supplements, current at the time of construction.

Initial Backfill: Backfill placed beside and over pipe in a trench, including haunches to support sides of pipe.

Inspector: An agent of the Utility assigned to make detailed inspections of any or all portions of the work and materials. The inspector has full authority to reject materials and/or any portion of the work not supplied and installed in accordance with these Standards or the approved plans and specifications.

Land Disturbing Activity: Any manmade change of the land surface including removing vegetative cover, excavating, filling, transporting, and grading.

Local Government: The Town Council of the Town of Chandler, the Warrick County Commissioners, Area Planning Commission, County Council, and/or other departments.

Main Extension: Extension of the Distribution System that will serve new customers.

Maintenance Guarantee: Any security that may be required and accepted by the Town Council to assure that necessary improvements will function as required for a specific period of time.

Manhole: A storm or sanitary sewer structure, through which a person may enter to gain access to a storm or sanitary sewer or other enclosed structure. A manhole may also be an inlet for the storm sewer system.

Manufacturer: The producer of those materials required by these Standards having direct responsibility and authority for the satisfaction of those minimum material specifications set forth herein.

Monument: A permanent marker conforming to the requirements of this Ordinance used to identify the location of a property corner or other survey information.

Non-Residential Subdivision: A subdivision whose intended use is other than residential, such as commercial or industrial.

Official Zoning Map: The map established by the local government, pursuant to law, showing the streets, highways, parks, drainage systems and setback lines laid out, adopted, and established by law, and any amendments or additions resulting from the approval of subdivision plats by the local government and the subsequent filing of the approved plats.

Off-Site: Any premises not located within the area of the property to be subdivided, whether or not in the common ownership of the applicant for subdivision approval.

Other Specifications and Materials: Wherever in these Standards other specifications or regulations are mentioned, it shall be understood that the materials and methods mentioned therewith shall conform to all requirements of the latest revision of the specifications so mentioned.

Owner: Any individual, partnership, firm, corporation or other entity who, as property owner, is initiating the work.

Pavement: That part of a street having an improved surface or brick, paving stone, concrete, or asphalt placed on the surface of the land.

Plans: Construction plans, including system maps, sewer plans, and profiles, cross sections, utility plans, detailed drawings, etc., or reproductions thereof, approved or to be approved by the Town Engineer which show location, character, dimensions and details of the work to be done.

Primary Plat: The primary drawing or drawings, indicating the proposed layout of the subdivision to be submitted to a town or county Planning Commission for approval.

Products: Items purchased for incorporating into the Work. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.

Professional Engineer: A person registered as a professional engineer by the Indiana State Board of Registration for Professional Engineers under IC 25-31.

Project: All work to be completed under the Town's permit in accordance with the approved plans, specifications, these Standards and the permit conditions.

Record Drawings (As-Built): Plans certified, signed and dated by a professional engineer or professional surveyor registered in the State of Indiana, indicating that the Plans have been reviewed and revised, if necessary, to accurately show all as-built construction and installation details including, but not limited to, key elevations, locations, and distances.

Registered Engineer: See "Professional Engineer"

Right-of-Way: A strip of land occupied or intended to be occupied by a street, crosswalk, railroad, road, electric transmission line, oil or gas pipeline, water main, sanitary or storm sewer main, shade trees, or for any other special use. The usage of the term "right-of-way" for land platting purposes shall mean that every

right-of-way hereafter established and shown on a secondary plat is to be separate and distinct from the lots or parcels adjoining such right-of-way and not included within the dimensions or areas of such lots or parcels. Rights-of-way intended for streets, crosswalks, water mains, sanitary sewers, storm drains, shade trees, or any other use involving maintenance by a public agency shall be dedicated to public use by the maker of the plat on which such right-of-way is established.

Sewer: A pipe or conduit for carrying wastewater (sanitary sewer) or storm water (storm sewer).

Sidewalk: A paved, surfaced, or leveled area, usually parallel to and separate from the street, used as a pedestrian walkway.

Specification: A detailed instruction that designates the quality and quantity of materials and workmanship expected in the construction of the project.

Standard Details: The drawings of structures, water mains, water service lines, fire hydrants, valves or other devices commonly used and referred to on the Plans and in these Standards.

Standards: The Water main Design and Construction Standards for the Town of Chandler, Indiana as contained herein and all subsequent additions, deletions, or revisions.

Structure: Anything constructed or erected which requires permanent location on/in the ground as part of the facilities installed.

Substantial Completion: The time at which the Work (or a specified part thereof) has progressed to the point where, in the opinion of the Engineer or the Town, the Work (or a specified part thereof) is sufficiently complete, in accordance with the project plans and specifications, so that the Work (or a specified part thereof) can be utilized for the purposes for which it is intended. The terms “substantially complete” and “substantially completed” as applied to all or part of the Work refer to Substantial Completion thereof.

Subsurface Drain: A tile drain installed for the purpose of lowering the ground water table.

Ten State Standards (Water Works): Recommended Standards for Water Works, latest edition, developed by the Committee of the Great Lakes – Upper Mississippi River Board of State and Provincial Public Health and Environmental Managers.

Town: The Town of Chandler, Indiana

Town Engineer: Authorized Agent by the Town of Chandler.

Utility: The Town of Chandler Utilities Department.

Water Distribution System: The collection of water mains interconnected to form a system of pipes, valves, hydrants, and appurtenances that can safely transport potable water from the Town's treatment facilities to the individual customers' plumbing throughout the service area.

Work: All the work to be done, in accordance with the approved Plans, Specifications, these Standards and permit conditions necessary for the successful completion of the project.

2 THE DEVELOPMENT REVIEW PROCESS FOR WATER MAIN CONSTRUCTION

2.1 GOALS AND OBJECTIVES

The Town of Chandler and Chandler Utilities are dedicated to encouraging growth and development. This review process has been implemented in effort to provide clear and concise instructions to builders and investors that do business within the Town of Chandler and the service area of Chandler Utilities.

The goals and objectives of this document are listed below.

- 1) Encourage a stronger local economy.
- 2) Clearly define and streamline a review and permitting process.
- 3) Establish expectations of contractors, builders, and developers.
- 4) Provide standard forms, documents, and details for use by developers, contractors, and engineers.
- 5) Outline the preferred brands, models, and configurations of water mains and water main appurtenances of Chandler Utilities.
- 6) Outline typical construction procedures.

Deviations from these standards may be approved by Chandler Utilities when proper justification is provided and approved.

Chandler Utilities is committed to unparalleled customer service through compliance with these standards, short project review timeframes, and consistent communication. All developers and contractors that construct water mains within the Town of Chandler or service area of Chandler Utilities are expected to follow the procedures and processes of this manual.

2.2 GENERAL

The Town of Chandler and Chandler Utilities are responsible for providing safe, clear, odorless, and tasteless drinking water to their residents and customers. To provide this service, Chandler Utilities must ensure proper installation and testing of all potable water distribution facilities constructed in or connected to existing facilities within the water service area. All facilities shall be designed and constructed in accordance with these Standards as well as applicable State / Federal regulations. The ordinances for water distribution systems governing these Standards are available for review at the Town of Chandler Utility Maintenance Facility.

The purpose of these Standards is to define a development review process, clearly communicate the Utility's expectations to potential customers, and establish minimum criteria for the design, installation, and testing of potable water infrastructure. This manual and the associated documents are intended to promote and encourage development within the Chandler Utilities service area. These water main Design and Construction Standards shall have jurisdiction over the entire Chandler Utilities service area, excluding water storage tanks and booster stations, from the point of discharge from the water treatment facility to the point of connection with the building plumbing or meter pit.

Addenda and/or revisions to these Standards may be issued periodically and will be distributed and made


available to the public and Contractor at the Utilities Office. Users shall be responsible to keep apprised of any changes and revisions to these Standards.

Any conflicts between these Standards and any applicable State laws shall be superseded by such law. If any conflict arises between these Standards and applicable Town or County Ordinances, the most recently adopted of the two shall prevail. These Standards are approved and adopted by the Town Council, Town of Chandler.

It is the Developer’s responsibility to comply with all requirements of the Utility or other authority having jurisdiction (AHJ) if such authority imposes greater requirements. Furthermore, the Developer shall be responsible for procuring all necessary permits and licenses, bonds, pay all charges and fees for acquiring and recording required easements, and giving all notices necessary and incidental to the work.

2.3 DEVELOPMENT REVIEW PROCESS DESCRIPTION

Water main construction within the Chandler Utilities service area is typically permitted through a review process directly with the utility. This process is illustrated in the flow chart shown in **Figure 1-1**.



No services will be activated until the entire development review process is complete.

Figure 1-1: Development Review Flow Chart

2.3.1 Preliminary Design Package, Technical Review, and Comments

The Developer shall submit preliminary design submittal to the Utility for review. This submittal shall include two (2) twenty four (24) inch by thirty six (36) inch plan sets signed and sealed by a professional engineer licensed in the State of Indiana, preliminary flow demand calculations, preliminary cost estimate, and all applicable state / federal permit applications.

The Utility shall review the documentation and provide written comments within thirty (30) days of receipt. Written comments shall include, but are not limited to, a letter describing required revisions, a red-lined plan set, and a list of additional items required for submittal with the final design package.

2.3.2 Final Design Package, Technical Review, and Final Plan Approval

The Developer shall address *all* concerns and comments from the Utility. The Developer shall resubmit final design package to the Utility for review, comment, and approval. This submittal shall include two (2) twenty four (24) inch by thirty six (36) inch plan sets signed and sealed by a professional engineer licensed in the State of Indiana, final flow demand calculations, final cost estimate, and any revised state / federal permit applications.

The Utility shall review the documentation for completeness and compliance within thirty (30) days of receipt. Satisfactory submittals shall be approved and signed state / federal permit applications returned to the Developer. The Utility may elect to issue an additional request for revisions only if initial comments and concerns are not fully addressed.

2.3.3 State and Federal Permits

The Developer shall provide copies of all applicable approved state / federal permits to the Utility prior to construction commencement. These permits may include, but are not limited to, Indiana Department of Environmental Management (IDEM) construction permit, IDEM Section 401, United States Army Corps of Engineers (USACE) Section 404, and IDEM Rule 5.

2.3.4 Posting of Bond

The Developer may be required to post a performance bond and maintenance bond issued by a company licensed by the State of Indiana to provide such surety. Each bond shall be equal to 100% of the contract amount or an amount established by the Utility to provide surety for the satisfactory completion of the improvements. The bonds shall name the Town of Chandler as a party who can enforce the obligations included. The duration of each bond shall be one (1) year.

The Utility may, as an alternative to the posting of such bond, accept other appropriate security such as a properly conditioned irrevocable letter of credit which meets the same objective as the bonds described in this section, subject to approval of any other department or agency whose interests are protected by the same bonding requirement. The bank issuing the letter of credit must be a bank situated in Indiana and must be an FDIC insured institution.

If the surety on any bond furnished to the Utility becomes a party to a supervision, liquidation, rehabilitation action pursuant to IC 27-9 et. seq. or its right to do business in the State of Indiana is terminated, it shall be

required that, within 30-days thereafter, a substitute bond and surety be provided, both of which must be acceptable to the Utility. Failure to obtain a substitute bond within the stated time frame shall be cause for revocation or suspension of the project approval until such time that the bond is furnished to the Utility.

2.3.5 Pre-Construction Coordination

The Developer shall schedule a preconstruction meeting a minimum of forty eight (48) hours prior to construction commencement of any water distribution systems. A Utility representative, engineering representative, and contractor are required to attend. At or before this meeting, the Developer shall provide the Utility with two (2) copies of the approved construction plans.

2.3.6 Construction Inspection and Observation

Chandler Utilities provides inspection, observation, and witnessing services for all public water main construction and testing. Basic inspection, observation, and witnessing services include the following:

- Coordination of water service, water meter, and fire hydrant locations.
- Coordination of taps and valves.
- Main line taps (hot taps and cut-ins)
- Hydrostatic pressure testing of mains and fire lines up to the building.
- Haunching and backfilling.

Inspection services not listed may result in additional fees required from the Developer. These fees will be assessed at the current hourly rate for Chandler Utilities staff. The Developer's Contractor is expected to be able to install the water mains and appurtenances in accordance with the approved contract documents with only basic inspection services. No action with regard to the Letter of Final Acceptance and release of the performance bond shall be taken until the Developer has reimbursed the Utility in full for any inspection services above and beyond the items listed above. All construction of public works facilities intended for dedication to the Utility shall be observed and certified pursuant to the Permit.

2.3.7 Project Acceptance and Dedication

Water distribution facilities will not be accepted and final pay request (if needed) will not be issued until all documents, as required by the Utility, are submitted to and approved by the Utility, including the following:

- Record drawings showing State Plane Coordinates and elevations to 0.1 foot on all valves and fittings. The Developer's Contractor shall submit two (2) copies of the record drawings and an electronic copy in Autocad format to the Utility. Record drawings shall show actual locations (northings and eastings) and depths of water mains, valves/valve boxes, fire hydrants, service taps, curb stops, meter pits and any other underground facilities installed as part of the project, including service line locations and depths.
- Letter of Substantial Completion (if required)
- Preliminary Inspection Report or Punch List (if required)

- Final Inspection Report
- Certified results of all testing that was performed including, but not limited to, hydrostatic pressure testing and bacteriological testing.
- One (1) Year Warranty
- Release of Lien (if required)
- Recorded Covenant and Easement Documents
- Operating and Maintenance manuals, parts lists, tools, list of products, etc. as applicable.

Upon approval by Chandler Utilities, the final pay request will be authorized and performance bond released if needed.

3 STANDARD DEVELOPMENT REVIEW FORMS

3.1 DEVELOPMENT PROCEDURES FOR WATER MAIN CONSTRUCTION CHECKLIST

**CHANDLER UTILITIES
TOWN OF CHANDLER, INDIANA**

**PROCEDURES FOR WATERMAIN CONSTRUCTION
(CHECK LIST)**

Date
Received/
Requested

Date
Appr./
Sent

PROJECT NO.: _____

PROJECT NAME: _____

- | | | |
|-------|-------|--|
| _____ | _____ | 1. Initial Coordination meeting including Developer and Utility Representative(s). |
| _____ | _____ | 2. Developer submits preliminary design package to Utility including application, two (2) 24-inch by 36-inch plan sets, preliminary flow demand calculations, preliminary cost estimate, application fees, and all applicable State / Federal permit applications. |
| _____ | _____ | 3. The Utility will review the plans for completeness, conformance with the Town's standards, and evaluate whether the existing water distribution system can supply the domestic and fire flows needed by this project. The Utility will identify necessary changes to the plans or specifications. |
| _____ | _____ | 4. The Utility will provide a review letter, red-lined plan set, and list of additional items required for approval within thirty (30) days of receipt of initial design package. |
| _____ | _____ | 5. Developer submits final design package to Utility addressing all concerns and comments including two (2) 24-inch by 36-inch plan sets, final flow demand calculations, final cost estimate, and all applicable State / Federal permit applications. |
| _____ | _____ | 6. The Utility will review the plans for completeness, conformance with the Town's standards. Upon satisfactory review, the Utility will issue recommendation of approval and return signed State / Federal permits to the Developer within thirty (30) days of receipt of final design package. |
| _____ | _____ | 7. Developer procures all applicable State / Federal permits and transmits to Utility. |
| _____ | _____ | 8. Developer procures maintenance bond, performance bond (letter of credit or certified check may be accepted on a case by case basis) and insurance certificates and transmits to Utility. |

- | | | |
|-------|-------|--|
| _____ | _____ | 9. After payment of any additional required fees, the Utility will issue a letter of project approval. |
| _____ | _____ | 10. Developer schedules and conducts an onsite preconstruction meeting with Contractor, Utility Representative, and Engineer a minimum of twenty-four (24) hours prior to the commencement of any construction operations. |
| _____ | _____ | 11. Developer completes construction in accordance with the contract documents. |
| _____ | _____ | 12. Following installation of the water mains, the Developer's Contractor conducts pressure tests and disinfection tests on the new mains. A copy of all test results must be provided to the Town within 2 business days of the completion of the test. |
| _____ | _____ | 13. The Utility issues a Letter of Substantial Completion. |
| _____ | _____ | 14. The Developer submits two (2) sets of record drawings (as-builts) drawings (prints and digital) and any easements required for review. Utility will review the easements for approval. The easements must be recorded prior to submittal and based on as-built conditions. Record drawings (as-builts) drawings shall be certified by Surveyor licensed in the State of Indiana. |
| _____ | _____ | 15. The Utility's representative prepares a punch list for the project. |
| _____ | _____ | 16. The Developer's Contractor completes punch list items. |
| _____ | _____ | 17. The Utility's representative re-inspects the project. |
| _____ | _____ | 18. Developer submits One Year Warranty, Release of Lien, and Certified Testing Results to the Utility. |
| _____ | _____ | 19. The Utility accepts maintenance of the project when service is started. |
| _____ | _____ | 20. After payment of any remaining fees or reimbursable expenses, the Utility issues a Letter of Final Acceptance to the Developer. |

3.2 CHANDLER UTILITIES PLAN AND SPECIFICATION REVIEW CHECKLIST

**TOWN OF CHANDLER, INDIANA
PLAN & SPECIFICATION REVIEW CHECKLIST**

NAME OF PROJECT: _____

DESIGN ENGINEER: _____

I. Completeness and Conformance with Town Standards

A. Watermain Pipe & Fittings

1. Sizes _____
2. All Watermains Plan and Profile _____
3. Depth 3' Min to Top of Pipe _____
4. Pipe Materials _____
5. Pipe Bedding & Backfill Materials & Construction _____
6. Jack and Bore _____
7. Horizontal Directional Drill _____
8. Details Complete _____
9. Specs Complete _____
10. Separation, Horizontal and Vertical _____

B. Water Service Connections

1. Sizes _____
2. Tapping Saddle Type _____
3. Corporation Stop Type _____
4. Pipe Materials _____
5. Curb Stop Type _____
6. Water Meter Box and Meter Setter _____
7. Check Valves _____
8. Details Complete _____
9. Specs Complete _____

C. Valves

1. Types _____
2. Spacing _____
3. Materials _____
4. Valve Boxes _____
5. Air/Vacuum Release Stations _____
6. Details Complete _____
7. Specs Complete _____

D. Connections to Existing Water Mains

1. Details of Connections _____
2. Existing Water Main Sizes & Materials Indicated _____
3. Compare Existing Water Mains to Town Water Map _____

E. Other Utility Conflicts

1. Horizontal Separation of 10' Min to Sewer Lines _____
2. Vertical Separation of 18" to Sewer Lines _____
3. Horizontal & Vertical Separation Between Other Utilities _____

F. Miscellaneous

1. Min. Easement Width 15' _____
2. Engineer's Seal & Signature _____

- 3. Page Numbers, Set Complete _____
- 4. Specs Complete _____
- 5. North Arrow on Each Street _____
- 6. Benchmark Indicated on Plans _____
- 7. Scale Indicated on Plans _____
- 8. Roads Labeled _____
- 9. Contours Labeled _____
- 10. Existing & Final Grade Shown on Profiles _____
- 11. Check Additional Notes, Details, Spec. Sections _____

II. **Calculations**

- A. Design Flow
 - 1. Fire flow conditions _____
 - 2. Max. Day conditions without fire flow _____
 - 3. Average Daily Flow _____

III. **Cost Estimate**

- A. Preliminary and Final
 - 1. Quantities _____
 - 2. Unit Prices _____

PLAN REVIEW DATE: _____

LETTERS SENT: _____

PLANS RESUBMITTED: _____

APPROVAL DATE: _____

3.3 APPLICATION FOR WATER MAIN CONSTRUCTION



APPLICATION FOR POTABLE WATER CONSTRUCTION

Please submit this completed form to Chandler Utilities – 101 Constitution Court, Chandler, Indiana 47610 or maintenance@townofchandler.org with the preliminary design submittal.

*** Please be sure to include a .pdf of the construction plans and a copy of the Engineer's Opinion of Probable Construction Cost.**

Date:

Project Name:


Parcel Number(s):

Location:

Project Description: Choose all that apply.

| Services | Potable Water Distribution System | Water Main Extension | Fire Lines | Hydrants |
|----------|-----------------------------------|----------------------|------------|----------|
|----------|-----------------------------------|----------------------|------------|----------|

| Type of Use: | <u>Number Of Units:</u> | <u>Flow Per Unit</u> | <u>Flow</u> |
|---|-------------------------|----------------------|-------------|
| S/F Residential (Individually Metered Homes/Units) | | | |
| M/F Residential (Master-Metered - More than 1 Home/Unit per meter) | | | |
| Commercial (Describe on page 2) | | | |
| Industrial (Describe on page 2) | | | |
| Other (Describe on page 2) | | | |



APPLICATION FOR POTABLE WATER CONSTRUCTION

PROJECT NAME: _____

Further instructions for Commercial, Industrial, Other:

Show a detailed description of water consumption for commercial, industrial, or any other type of development by using 327 IAC 3-6-11 guidelines for each meter. Note, the total of these flows should be equal to the Total Average Daily Flow included on the Indiana Department of Environmental Management construction permit applications.

List number and sizes of water meters required for this development. Please include what each meter will serve.

* Please be sure to include a .pdf of the construction plans and a copy of the Engineer's Probable Cost Opinion.



APPLICATION FOR POTABLE WATER CONSTRUCTION

PROJECT NAME: _____

Developer Information:

Name of Developer &/or Owner: _____

Name and Title of Representative: _____

Mailing Address: _____

City, State & Zip: _____

Telephone Number: _____

E-mail Address: _____

Engineer Information:

Name of Engineering Firm: _____

Name of Project Engineer: _____

E-mail Address: _____

Alternate Contact Person: _____

E-mail Address: _____

Mailing Address: _____

City, State & Zip: _____

Telephone Number: _____

3.4 SUBSTANTIAL COMPLETION FIELD INSPECTION CHECKLIST

**TOWN OF CHANDLER, INDIANA
SUBSTANTIAL COMPLETION FIELD CHECKLIST**

NAME OF PROJECT: _____

INSPECTOR NAME: _____

CONTRACTOR REPRESENTATIVE: _____

A. Water Main Pipe

1. Size matches plans _____
2. Material matches plans _____
3. 36 inches of cover to top of pipe _____
4. 6 inches of bedding underneath the pipe _____
5. Crushed stone bedding for PVC pipe _____
6. Sand or crushed stone bedding for DIP _____
7. 6 inches of compacted backfill above pipe _____
8. Crushed stone backfill for PVC pipe _____
9. Class I or II backfill for DI pipe _____
10. Granular backfill under and adjacent to roadways _____
11. No stones larger than 3 inches in backfill _____
12. Compaction tests submitted _____
13. Pressure tests submitted _____
14. Chlorination and Bacteriological test submitted _____
15. Adequate vertical separation at crossing _____
16. Adequate horizontal separation from other utilities _____
17. Restrained joints at tees, bends, plugs, etc. _____

B. Valves

1. Valve boxes installed at grade _____
2. Valves open _____
3. Valve keys provided _____
4. Tracer wire brought to surface _____
5. Air release valves at high points _____
6. Blowoff assemblies are size on size _____
7. Blowoff assemblies 2' above grade _____

C. Services

1. Copper or polyethylene _____
2. Corp Stop at 22 degrees _____
3. Meter pit at grade _____

F. Miscellaneous

1. Fire Hydrant location acceptable _____
2. Fire Hydrant valve open _____
3. Granular bedding below hydrant _____
4. Restrained joints or thrust blocks at hydrant _____
5. _____
6. _____
7. _____
8. _____
9. _____

3.5 LETTER OF SUBSTANTIAL COMPLETION

**TOWN OF CHANDLER, INDIANA
LETTER OF SUBSTANTIAL COMPLETION**

OWNER's Project No.: _____ **CONTRACTOR's Project No.:** _____

Project: _____

CONTRACTOR: _____

OWNER: _____

Contract Date: _____

The Work performed under this Contract has been reviewed and found, to the best knowledge of the Town of Chandler or the Town representative to be substantially complete. Substantial Completion is the stage in the progress of the Work when the Work or designated portion is sufficiently complete in accordance with the Contract Documents so that the Owner can occupy or utilize the Work for its intended use. The date of Substantial Completion of the Project or portion designated above is the date of issuance established by this Certificate, which is also the date of commencement of applicable warranties required by the Contract Documents, except as stated below:

| | | |
|----------|----|------|
| ENGINEER | BY | DATE |
|----------|----|------|

A list of items to be completed or corrected is attached hereto. The failure to include any items on such list does not alter the responsibility of the Contractor to complete all Work in accordance with the Contract Documents. Unless otherwise agreed to in writing, the date of commencement of warranties for items on the attached list will be the date of issuance of the final Certificate of Payment or the date of final payment.

Cost estimate of Work that is incomplete or defective: \$ _____

The Contractor will complete or correct the Work on the list of items attached hereto within () days from the above date of Substantial Completion.

The responsibilities of the Owner and Contractor for operation, safety, maintenance, insurance, warranties, guarantees, and damage to the Work shall be as follows:

RESPONSIBILITIES:

OWNER: _____

CONTRACTOR: _____

| | | |
|---|----|------|
| CONTRACTOR | BY | DATE |
| The Contractor accepts this Letter of Substantial Completion. | | |

| | | |
|--|---------|------|
| OWNER | BY | DATE |
| The Owner accepts this Letter of Substantial Completion and will assume full possession at | | |
| (time) on | (date). | |

3.6 LETTER OF FINAL ACCEPTANCE

**TOWN OF CHANDLER, INDIANA
LETTER OF FINAL ACCEPTANCE**

OWNER's Project No.: _____ **CONTRACTOR's Project No.:** _____

Project: _____

CONTRACTOR: _____

OWNER: _____

Contract Date: _____

The Work performed under this Contract has been reviewed and found to be complete in accordance with the terms and conditions of the contract documents. The entire remaining balance of the contract is due and payable. The following items have been completed and accepted.

- ☐ Contractor's Final Pay Request Form is attached.
- ☐ All Punch List Items are complete and accepted.
- ☐ Letter of Substantial Completion has been issued by the Engineer.
- ☐ Record Drawings (as-builts) have been received, reviewed, and approved by the Owner.
- ☐ One-Year Warranty has been received by the Owner.
- ☐ Release of Lien has been received by the Owner.
- ☐ Certified pressure testing results have been received by the Owner.
- ☐ Certified bacteriological testing results have been received by the Owner.
- ☐ Required easements have been accepted by the Owner and recorded.
- ☐ Operating Manual, Parts List, Lists of Products, Maintenance Manuals, Operating Tools and Devices, Maintenance Materials, Extra Parts, etc. as required under the contract, have been accomplished.

| | | |
|---|----|------|
| CONTRACTOR | BY | DATE |
| The Contractor accepts this Letter of Final Acceptance. | | |

| | | |
|-------|----|------|
| OWNER | BY | DATE |
|-------|----|------|

The Owner accepts this Letter of Final Acceptance and agrees to release final payment and performance bond.

3.7 WATER AND SEWER UTILITY EASEMENT

**CHANDLER UTILITIES
TOWN OF CHANDLER, INDIANA**

**WATER & SEWER
UTILITY EASEMENT
(PERMANENT)**

Deed Record:

Owner:

THIS INDENTURE WITNESSETH, that _____ ("Grantor"), for and in consideration of the sum of _____ Dollars (\$ _____), and other valuable consideration, the receipt of which is hereby acknowledged, does hereby GRANT and CONVEY UNTO _____ ("Utility") whose principal place of business is _____, its successors, assigns, and lessees, a permanent water and sewer utility easement and right-of-way to the Real Estate described herein, for the purpose of granting and facilitating the right to lay, construct, inspect, maintain, operate, repair, alter, relocate, enlarge, rebuild and remove one or more pipe lines, transmission media, and all appurtenant and necessary structures, whether above or below the surface, convenient or necessary to transport and otherwise handle water and sewerage, and perform and facilitate such utility services over, along, across, within, and upon, Real Estate, together with the right of ingress and egress over the existing roads and entrances to the lands of Grantor to and from said Real Estate, in the exercise of the rights herein granted, provided, that in the exercise of such right the Utility will, whenever practicable to do so, use regularly established highways or roadways.

The real estate of Grantor upon, over and across which said easement and right-of-ways shall be laid out and located, is situated as part of _____, and is more particularly described in the attached **Exhibit "A" (Permanent Easement)** and depicted upon the Right of Way Parcel Plat attached hereto as **Exhibit "B"**, both of which exhibits are made a part hereof ("Real Estate").

Grantor for the same consideration further grants to the Utility the right to trim or remove any trees, brush, undergrowth or other obstructions from said easement and right-of-way, if necessary, in the exercise of the rights and privileges herein granted.

Subject to the rights herein granted to the Utility, the Grantor reserves the right to use and enjoy the land included with the easement and right-of-way, which includes parking, but no buildings, structures, fences, or any other type of improvement or property, either of a permanent or temporary nature, shall be located or maintained within the Real Estate, no excavating or grading shall be done within said Real Estate, which would reduce the coverage of soil over said pipe line or increase the coverage more than three (3) feet, and no lake or pond shall be constructed within fifteen (15) feet of either side of said Real Estate measured from the top edge of the bank of any such lake or pond.

The covenants and agreements herein contained and set forth as pertains to this easement as granted herein shall for all purposes be construed and considered as covenants and agreements running with and in favor of the title to said Real Estate and running with the title to said Real Estate, and shall be binding upon the parties hereto and their respective successors and assigns.

In the event that any of the provisions of this instrument shall be held by a court or other tribunal of competent jurisdiction to be unenforceable, such provision shall be enforced to the fullest extent permissible and the remaining portion of this instrument shall remain in full force and effect. This instrument represents a compromise between the parties and is a product of arms-length negotiations. The parties have read this instrument completely and have had the opportunity to seek the advice and assistance of competent legal counsel. In the event that ambiguity exists or is deemed to exist in any provisions of this instrument, said ambiguity is not to be construed by reference to any doctrine calling for such ambiguity to be construed against the drafter of this instrument. This instrument shall be governed by and construed in accordance with the laws of the State of Indiana, not including the choice of law rules thereof, and each party hereto by execution of this instrument, consents to the exercise of jurisdiction over any matter arising in connection with this instrument in the Superior Court of Vanderburgh County, State of Indiana. As used in this instrument, the plural shall be substituted for the singular, and the singular for the plural, where appropriate; and words and pronouns of any gender shall include any other gender. THIS PROVISION, AND EACH AND EVERY OTHER PROVISION OF THIS INSTRUMENT MAY NOT UNDER ANY CIRCUMSTANCES BE MODIFIED, CHANGED, AMENDED OR PROVISIONS HEREUNDER WAIVED VERBALLY, BUT MAY ONLY BE MODIFIED, CHANGED, AMENDED OR WAIVED BY AN INSTRUMENT IN WRITING EXECUTED BY ALL PARTIES HERETO.

The above described permanent sewer utility easements is a part of the Grantor's property as described in the Office of the Recorder of Warrick County, Indiana.

IN WITNESS WHEREOF, the Grantor has have executed this Easement as of the _____ day of _____, 2015.

By: _____
(signature)

(printed name and title)

STATE OF _____)
) SS:
COUNTY OF _____)

BEFORE ME, a Notary Public in and for said County and State, personally appeared _____, as the _____ of _____, who acknowledged the execution of the foregoing instrument and who, having been duly sworn, stated that any representations therein contained are true.

IN WITNESS WHEREOF, the parties have duly executed this instrument, and I have hereunto set my hand and official seal as of the _____ day of _____, 2015.

Notary Public

My Commission Expires:

Printed Name

My County of Residence:

This instrument was prepared by Joshua A. Claybourn, **JACKSON KELLY PLLC**, 221 N.W. Fifth Street, P.O. Box 1507, Evansville, IN 47706, Telephone (812) 422-9444

I affirm, under the penalties for perjury, that I have taken reasonable care to redact each Social Security number in this document, unless required by law.

Joshua A. Claybourn

RETURN TO:

Exhibit "A"

4 WATER DISTRIBUTION FACILITY DESIGN STANDARDS

4.1 GENERAL REQUIREMENTS

All water mains shall be designed in accordance with IDEM, *Recommended Standards for Water Works* (commonly known as the 'Ten States Standards'), and 327 Indiana Administrative Code (IAC) and these standards. Any variances from these standards must be approved in writing by the Utility prior to the final design submittal. All design drawings used for permit applications, bidding, and construction shall be signed, dated, and sealed by a professional engineer licensed in the State of Indiana.

4.1.1 Specifications

Technical specifications shall be in accordance with IDEM, *Recommended Standards for Water Works* (commonly known as the 'Ten States Standards'), and 327 Indiana Administrative Code (IAC) and these standards. These specifications shall be prepared using an industry standard naming and number protocol such as the Engineers Joint Contract Documents Committee (EJCDC) or the American Institute of Architecture (AIA). Chandler Utilities does not provide a review of the project specifications. It is the responsibility of the Developer's Engineer to ensure that the specifications match the approved plans and meet regulatory code.

4.1.2 Permits

The Developer shall be responsible for obtaining all permits which relate to the design of the completed facilities. A copy of all permits shall be filed with the Town upon receipt and prior to beginning any work. Permits obtained by the Developer include, but are not limited to, permits from the following:

- Indiana Department of Environmental Management (IDEM)
- Indiana Department of Fire Prevention and Building Safety
- Indiana Department of Natural Resources (IDNR)
- U.S. Army Corps of Engineers
- IDEM Rule 5 – Storm Water Run Off Associated with Construction Activity
- Applicable County and local permits

4.1.3 Drafting Standards

Design drawings shall be twenty four (24) inch by thirty six (36) inch. The scale for plan and profile sheets shall not exceed 1"=30' Horizontal and 1"=5' Vertical. Each sheet shall contain a north arrow and bar scale. Each set of drawings shall also include the applicable detail sheets and construction notes. The design drawings shall be prepared in the current version of AutoCAD software. All design drawings should include the plat and approved addresses.

4.2 WATER MAINS

4.2.1 General Configuration

The water main configuration shall be designed to provide service to the front of each lot in the development and to the edge of the site being developed where it is likely that future developments will occur, as determined by the Town. In general, the layout of the water mains shall form a grid (sometimes called a looped system) with connections at each street intersection and wherever practical.

All water mains shall be located in a dedicated Water Facility Easement or within the public street right-of-way. Preferably the water main shall be located on the opposite side of the street from the sanitary and storm sewers. Water mains which cross roadways (i.e. streets, highways, etc.), railroads, and other utilities shall preferably do so at ninety (90) degrees whenever practical. The pipe should be designed so that the angle of intersection with the roadway is not be less than forty five (45) degrees.

Water mains shall be constructed with joint restraints at all taps, crosses, tees, bends, reducers, and fittings installed per manufacturer's specifications and Chandler Utility details. Thrust blocks are generally not permitted, but may be allowed on a case by case basis as determined by the Utility.

Water mains and services shall have a minimum cover of thirty six (36) inches per 327 IAC 8-3.2-17. Generally, water mains shall be eight (8) inches in diameter minimum although small sizes may be permitted by Chandler Utilities on a case by case basis.

4.2.2 Cul-de-sac Water Mains

Water mains in cul-de-sacs shall be extended to the end with a fire hydrant at the farthest property line. Cul-de-sac mains shall be a minimum of 6 inches.

4.2.3 Dead-end Water Mains

In general, dead-end water mains are not permitted. In the event that a dead-end water main is necessary or unavoidable, such as at a future extension of a street, the water main shall terminate with a gate valve downstream of the last potential service line connection (such that closing the valve does not put any customer out of service). This valve shall normally be closed when the water system is in use. Therefore, there must be either sufficient pipe installed downstream of said valve to provide the necessary thrust restraint or a concrete thrust block around the circumference of the pipe making a collar (sometimes called a dead-man restraint or straddle block) and individual joint restraints as needed for the particular situation. Whichever method of thrust restraint is used it shall allow for the connection to the very end of the dead-end water main for future extension without jeopardizing the thrust restraint at the valve in any way or put any customer out of service. Furthermore, a fire hydrant or same size blow off shall be installed at the end of the pipe to facilitate manual flushing when needed. In the case of a future street extension, a valve and same size blow off is to be installed.

4.2.4 Easements

The minimum width for water facility easements shall be fifteen (15) feet, unless otherwise authorized by the Utility. All water lines shall be centered in the easement unless a sewer (either storm or sanitary) is also present. In that case, a minimum of ten (10) feet separation must be maintained between the water line and the sewer line, and additional easement widths may be required as determined by the Utility.

The easements shall be exclusively under the discretion and control of the Utility. Ingress and egress shall be available to the Utility's crew at all times. No other utility companies are allowed to use the easements for installation of their utility lines without the expressed written permission of Chandler Utilities. All plans sheets shall clearly identify the existing and proposed easement and the location of all other proposed utilities.

4.2.5 Separation of Water Mains and Sewers

Separation requirements shall comply with 327 IAC 8-3.2-9. Generally, water mains and service lines shall be installed at least ten (10) feet horizontally from any existing or proposed sewer or lateral. The distance shall be measured edge to edge. In cases where it is not practical to maintain a ten (10) foot separation, the appropriate reviewing agency may allow deviation on a case-by-case basis, if supported by data from the design engineer. Such deviation may allow installation of the water main or service line closer to a sewer or lateral, provided the water main is in a separate trench or on an undisturbed earth shelf located on one side of the sewer or lateral and at an elevation so the bottom of the water main is at least eighteen (18) inches above the top of the sewer or lateral.

Water main and service lines crossing sewers and laterals shall be installed to provide a minimum vertical distance of eighteen (18) inches between the outside of the water main or service line and the outside of the sewer or lateral. This shall be the case where the water main or service line is either above or below the sewer or lateral. The crossing shall be arranged so that the joints of the water main or service line will be equidistant and as far as possible from the sewer or lateral joints (the pipe shall be centered on the crossing). Generally, the water main shall cross over the sewer pipe. Where a water main or service line crosses under a sewer or lateral, adequate structural support shall be provided for the sewer or lateral to maintain line and grade.

When it is impossible to obtain proper horizontal and vertical separation as stipulated above, one of the following methods must be specified:

- Both the water main and sewer or lateral shall be constructed of ductile iron CL350 mechanical joint pipe complying with public water supply design standards of the agency and be pressure tested to 150 psi to assure water tightness before backfilling.
- The sewer or lateral shall be designed and constructed equal to water pipe and shall be pressure-tested at 150 psi to assure water tightness prior to backfilling.
- Either the water main or service line or the sewer or lateral line may be encased in a watertight carrier pipe which extends ten (10) feet on both sides of the crossing, measured perpendicular to the sewer or lateral. The carrier pipe shall be of materials approved by the regulatory agency for use in water main construction.

Water mains shall not be located closer than ten (10) feet from any existing building structure or foundation or any building set back limit for future building structures.

4.2.6 Design Flows & Pressures

The Utility will provide current flow test(s) information as near to the point(s) of connection between the proposed site and the existing water distribution system as deemed practical and useful. The Developer's Engineer may rely on this information to design the water mains for the proposed site taking into account the portion(s) of the existing water distribution system between the location of the flow test(s) and the proposed site. The C factor used in the hydraulic calculations (using Hazen-Williams equation) for ductile iron pipes up to

five years old shall be 120 and for pipes up to ten years old shall be 115. Ductile (or cast) iron pipes older than ten years shall use a C value of 100.

All water mains shall be sized & looped to provide a min. of thirty five (35) psi, measured at ground level at the highest proposed elevation within the site, under peak hour flow conditions and a min. of twenty five (25) psi, same measurement method, under fire flow conditions. If at any point during construction, the water main pressure drops below twenty (20) psi, the Developer's Contractor must immediately contact Chandler Utilities.

Water quantity and the peak hour flow condition shall be determined based on 327 IAC 8-3.3-2.

Commercial and industrial properties shall compute required fire flow in accordance with the ISO Guide for Determination of Needed Fire Flow latest edition.

If these design criteria cannot be met with connections to the existing water distribution, the Utility will use their hydraulic model of the existing distribution system to confirm that assertion and, if valid, the Utility will use the hydraulic model to identify water distribution system reinforcements (i.e. additional pipes, upsizing of existing pipes, etc.) needed to meet these design criteria. The Developer will be then be required to design those water distribution system improvements. Those designs must also comply with these standards and in the event there are issues with such design which are not sufficiently addressed the Utility will provide additional design standards to address the issues at hand.

Furthermore, the Town may require the upsizing of certain sections of the water main to provide sufficient flow to future or existing sites within the Town's water service area. The responsibility for the cost to upsize the water mains shall be negotiated during permitting.

4.2.7 Special Crossings

Railroads, streams, rivers, etc. are considered special crossings. Special crossings shall be installed in accordance with the AHJ permit such as the USACE, IDNR, IDEM, or the railroad company. The preferred installation method for stream crossings is by horizontal directional drill (HDD) using fusible PVC pipe. HDD installation of restrained joint PVC pipe or High Density Polyethylene (HDPE) pipe under streams may be permitted in some cases. Special crossings are subject to the separation requirements of Section 4.2.5. Isolation valves shall be located on either side of the crossing outside of the one hundred (100) year floodplain.

In channel disturbance and open cut installation methods through stream, creeks, and rivers is prohibited. Aerial crossings are also prohibited.

4.2.8 Valves

Valves shall be located at the three (3) branches of a tee and at the four (4) branches of a cross fitting. The maximum length of a section of water main to be shutdown is six hundred (600) feet in residential areas and commercial areas per 327 IAC 8-3.2-14. A water main valve shall also be located on the main at fire hydrants on the side of the water main that has the greatest distance to the next in line isolation valve. The spacing in industrial areas will be evaluated, by the Utility, on a case by case basis. Air release valves shall be provided at all

isolated high points within the system. The contractor shall provide, but not install, a location marker with all valves installed on the project.

4.2.9 Fire Hydrants

In general fire, hydrants should be located within two hundred (200) feet of a commercial or industrial building and within fifty (50) feet of the Fire Department Connection (FDC). The maximum spacing between fire hydrants in residential and commercial areas is six hundred (600) feet per 327 IAC 8-3.2-15. A fire hydrant shall be provided at all cul-de-sacs. Fire hydrants shall not be connected to a main less the six (6) inches diameter and will maintain three (3) feet of separation from any existing utility. Every fire hydrant shall be installed with a drainage pit of at least one half (1/2) cubic yard of open graded crushed stone.

4.3 WATER SERVICE LINES

4.3.1 General Configuration

The water service configuration shall be designed to provide service to the front of each lot in the development with meter box located and centered on the right-of-way line.

Water service line ownership is separated at the meter. Chandler Utilities maintains ownership and maintenance from the water main tap up to and including the double check valve assembly to a point approximately ten inches outside the meter box or the first connection outside the meter box. The property owner is responsible for owning and maintaining the water service line from the downstream side of the double check valve to the structure. Services shall be constructed in manner that minimizes bends, deflections, and excessive depths.

Chandler Utilities may require the developer to install casings / conduits for future water services during the development review process.

4.3.2 Design Flows and Pressures

Design flows for single family homes shall be determined in accordance with 327 IAC 8-3.3-2 which states that the average daily consumer demand for residential service connections is five hundred (500) gallons per day. A peaking factor of two and a half (2.5) shall be used to determine peak demand. Design flow for commercial and industrial developments shall be determined in accordance with Table 2-1 of 327 IAC 8-3.3-2 available online.

Water service lines will be sized to deliver water service at a minimum thirty five (35) psi. The minimum water service line size shall be three quarters (3/4) of an inch. Bypass lines may be required as determined by the Utility.

4.3.3 Valves

The Developer shall provide valves sufficient to construct, modify, and maintain the water service without disrupting the main or adjacent services. Typical water service lines shall have a corporation stop at the tapping saddle, curb stop at the water meter, and double check valve on the downstream side of the meter.

Larger residential water services may require additional valves as determined by Chandler Utilities.

4.3.4 Meters

Chandler Utilities will provide and install new water services up to two (2) inches. Chandler Utilities will provide meters great than two (2) inches. Meters greater that two (2) inches will be installed by the Developer's Contractor. Water services are typically installed to the right-of-way line with the top of the meter box flush with adjacent grade. No meter box is permitted more than three (3) inches above adjacent grade. Chandler Utilities will provide and install the tapping saddle, corporation stop, service line, meter box, meter setter, and meter.

It is the responsibility of the Developer's General Contractor to maintain the integrity of the meter, meter pit, and all adjacent appurtenances once installation is complete. Any damages incurred by these devices shall be the financial responsibility of the Developer's General Contractor.

4.3.5 Backflow Prevention

Backflow prevention, also known as cross connection control, shall be provided in accordance with 327 IAC 8-10. Chandler Utilities requires the use of a double check valve assembly on the downstream side of the water meter for residential applications. Commercial and industrial cross connection control shall be in accordance with Indiana building and plumbing code.

5 MATERIALS STANDARDS FOR WATER MAINS

5.1 GENERAL

This section provides a list of the materials acceptable for the construction of water distribution facilities. Additional materials and brands may be permitted by the Utility on a case by case basis. Hardware for appurtenances and fitting shall be stainless steel or bronze. Galvanized materials are not permitted.

The Town of Chandler and Chandler Utilities prefers the use of domestically manufactured products. All materials provided by developers or contractors must be purchased from a local approved, authorized dealer when possible such as J and J Supply, Inc. (Booneville) and Utility Supply Company (Huntingburg). Chandler reserves the right to request any information pertaining to the dealers or venders providing the materials. Chandler has the right to refuse any material or equipment submitted for a project.

Projects funded by state and federal grants or loans shall conform to all material manufacturing requirements of the funding agency.

5.1.1 Water Mains

The following materials are acceptable for water mains:

- 1) Polyvinyl Chloride (PVC) – SDR 21, DR 18, DR 14, DR 21, C905
 - a. Typical Accepted Manufacturers
 - i. JM Eagle
 - ii. Pipelife
 - iii. North American Pipe
 - iv. Northern
- 2) Ductile Iron (DI) – Pressure Class 350
 - a. Typical Accepted Manufacturers
 - i. U.S. Pipe
 - ii. McWane

5.1.2 Water Main Fittings

The following manufacturers and materials are acceptable for water main fittings:

- 1) Joint Restraints
 - a. Typical Accepted Manufacturers
 - i. EBAA Iron Series 2000PV
 - ii. Ford / Uni-Flange
- 2) Tapping sleeves
 - a. Typical Accepted Manufacturers
 - i. Romac Industries Stainless Steel
 - ii. JCM Industries Stainless Steel

5.1.3 Water Services

The following manufacturers and materials are acceptable for water services:

- 1) Copper Tubing, Type K or M
 - a. Typical Accepted Manufacturers
 - i. Mueller Industries
 - ii. JB Industries
 - iii. Weiland Copper Products
- 2) Polyethylene (PE) – SDR 9
 - a. Typical Accepted Manufacturers
 - i. Uponor
 - ii. Endot Industries
- 3) Meter Setters

Meter setters shall be twelve (12) inch tall with ball valve and double check cartridge.

 - a. Typical Accepted Manufacturers
 - i. AY McDonald
 - ii. Ford
- 4) Tapping Saddles

Tapping saddles shall be all brass hinge type.

 - a. Typical Accepted Manufacturers
 - i. AY McDonald
 - ii. Ford

5.1.4 Valves

5.1.4.1 Gate Valves

Gate valves shall be AWWA approved resilient seated, cast iron or ductile iron, with stainless steel stems.

- a. Typical Accepted Manufacturers
 - i. Mueller
 - ii. Clow
 - iii. East Jordan

5.1.4.2 Air/Vacuum Release Valves

Air/vacuum release valves shall be automatic hydromechanical, cast iron, and AWWA approved.

- a. Typical Accepted Manufacturers
 - i. Val Matic
 - ii. Apco

5.1.4.3 Corporation Stops and Curb Stops

Corporation Stops and Cub Stops shall be tapered thread ball valve style and AWWA approved.

- a. Typical Accepted Manufacturers
 - i. Mueller
 - ii. Ford
 - iii. AY McDonald

5.1.5 Appurtenances

5.1.5.1 Hydrants (Revised 10-1-2018)

Fire Hydrants shall be domestically produced, dry-barrel, compression shut off, traffic model design and shall comply with ANSI/AWWA C502.

Inlets shall be a minimum 6" mechanical joint. Each hydrant shall have two 2-1/2-inch nozzles and one 5-inch Storz connection fitting. The hydrant shall have a positive , non-corrodible type bronzed lined drain valve. When the hydrant is open the drip valve will close the drain and when the hydrant is closed the drain will open. The operating nut and the two 2-1/2-inch caps shall have a 1-1/2 inch pentagon nut. The two 2-1/2 inch caps shall not have chains attached. The 5-inch Storz cap shall have a jacketed stainless-steel cable attaching the cap to the main body of the hydrant.

All hydrants shall open left. Each hydrant shall be buried at the proper depth for the water main to which the hydrant is connected. Hydrants shall be furnished with mechanical joint accessories including bolts, glands, and gaskets.

All hydrants shall have stainless steel hardware above and below grade including the upper and lower stems. Fire hydrant coatings shall meet the requirements of ANSI/AWWA C502 Fire hydrant coating shall be red.

a. Typical Accepted Manufacturers

- i. Mueller
- ii. Clow
- iii. East Jordan

5.1.5.2 Tracer Wire

Tracer wire shall be installed on the top of all PVC water mains. Wire shall be minimum of #12 solid copper wire with thermoplastic insulation capable of carrying thirty (30) volts.

a. Typical Accepted Manufacturers

- i. Copperhead

5.1.5.3 Valve Boxes / Meter Boxes

a. Typical Accepted Manufacturers

- i. Carson
- ii. Oldcastle
- iii. Tyler Union
- iv. Sigma

5.1.5.4 Valve Vaults

Valve vaults shall be precast construction and include the following:

- 1) 4,500 PSI concrete in accordance with ASTM C-913
- 2) U.S. Foundry (or equal) aluminum hatch 30" x 36"
- 3) Kor-N-Seal Connectors
- 4) Cast iron floor drain cast into structure
- 5) Waterproof butyl mastic sealant on the outside of structure

6 INSTALLATION AND CONSTRUCTION OF WATER MAINS

6.1 GENERAL

This section shall provide general, minimum requirements for the installation and construction for Chandler Utilities water distribution projects. This installation guidelines can be modified as approved during permitting and construction by Chandler Utilities.

6.1.1 Safety

Neither the Utility, Town, nor its representatives are responsible for safety on the job site. All codes, statutes and regulations relating to safety on the job site shall be followed by the Owner, Developer and Contractor. Direction by the Utility's representative is not designed to assure safety on the job, only that the water distribution system is built according to these standards and the drawings.

6.1.2 Excavation

6.1.2.1 Dewatering and Control of Surface Water

The Developer's Contractor shall make every effort necessary to secure a dry trench bottom before laying pipe. The Contractor shall provide, install and operate sufficient trenches, pumps, hoses, piping, well points, etc. necessary to lower and maintain the groundwater level below the base of the excavation. If the Contractor is unable to remove the standing water in the trench, the Contractor shall over-excavate the proposed bottom grade of the sewer bedding, and place not less than 3 inches of Class No. 8 crushed stone (per INDOT aggregate classification) in the over-excavated area. The Contractor shall make every effort to maintain a work site free of surface water shall install drainage ditches, berms, pumps and perform other work necessary to divert runoff away from excavations. Any water discharged from dewatering operations shall be treated for sediment removal prior to discharge to surface waters. Under no circumstances shall surface water and/or groundwater be discharge to, disposed of, or allowed to flow into the Town's Sanitary Sewer System.

6.1.2.2 Site Preparation

Before the commencement of any excavation, adequate protection shall be provided for all lawns, trees, landscape work, shrubs, fences, utilities, sidewalks, and other objects that are to remain in place. Such protection shall be maintained for as long as necessary to prevent damage from the Contractor operations.

Moveable items such as mail boxes and roadway signs may be temporarily relocated during construction. Place moveable items in their original location immediately after backfilling is complete. Moveable items damaged during construction shall be replaced with new items at the Contractor's expense.

Strip topsoil and vegetation from the excavated areas. Clean topsoil may be stockpiled for re-use as the upper 6-inches of the area to be seeded. Do not intermix grass, weeds, roots, brush, and stones larger than 1 inch with stockpiled topsoil. Legally dispose of root contaminated topsoil.

Clear and remove logs, stumps, brush, vegetation, rubbish and other perishable matter from the job site. Do not remove or damage trees that do not interfere with the work. Completely remove trees including stumps and roots that are required to be removed.

Remove existing pavement and walks from the areas to be excavated and dispose in a legal manner. Use methods, such as saw cutting, to remove pavement and concrete walks that will assure the breaking or cutting along straight and vertical lines. Remove walks completely where excavation is along the length of a walk to existing joints.

6.1.2.3 *Excavating*

Excavated materials suitable and necessary for backfilling shall be stored in a neat pile adjacent to the excavation and protected by erosion control measures. Such materials shall not be placed with at a height or proximity to excavation that may endanger the trench sidewalls due to earth slides or cave-ins.

Excavated material not suitable for backfilling and excess suitable material shall be removed from the job site and legally disposed of in a spoil area secured by the Contractor and approved by the Town.

Provide dewatering in accordance with section 6.1.2.1.

6.1.2.4 *Trenching*

Excavate trenches to a depth and width as required by the pipe manufacturer for proper installation of the pipe and appurtenances. Excavations below the required grade shall be filled with compacted bedding or granular material.

Trenches shall be made as narrow and straight as possible. Sides of trenches shall be kept as near vertical as possible and shall be properly sheeted and/or braced, if required. The Contractor shall provide adequate sheeting and bracing in open cut trenches to protect life, property and the work. All sheeting, planking, timbering, shoring, bracing, and bridging shall be placed, renewed and maintained, and shall not be removed until sufficient backfill has been placed to protect the pipe. Benching is permitting where sufficient space is available. Benching shall be installed no steeper than two (H) to one (V).

Provide a continuous, uniform bearing support for the pipe on solid undisturbed soil or compact granular fill with trench dished to provide circumferential support to the lower third of each pipe along the entire length of the pipe, including pipe bells.

Rock excavation encountered in the trench and soft material which, in the opinion of the Town is incapable of providing adequate bearing to support the pipe, shall be removed to a depth of 4-inches below the required elevation and filled with compacted No. 8 aggregate.

Do not open more than fifty (50) feet of trench in advance of the installed pipe. Excavate the trench within six (6) inches of full depth for a distance of at least thirty (30) feet in advance of the pipe installation.

Maintain one lane of traffic at all streets and service drives during construction. Streets and drives may be closed and traffic detoured if permission is obtained by the Contractor from the AHJ.

Any sewer, gas, water, or other pipes or conduits crossing the trench shall be supported without damage and without interrupting service. The manner of supporting such pipes or conduits shall be subject to the approval of the Town and/or the utility involved.

Where rock is encountered during trenching operations, the Contractor may remove the rock by mechanical means. The use of a hoe ram breaker is the preferred method of removal. Rock trenchers are also acceptable. Blasting will not be permitted.

No farm fences shall be cut when gates are available within a reasonable distance to move equipment from one field to another.

Provide dewatering in accordance with section 6.1.2.1.

6.1.3 Bedding and Backfill

6.1.3.1 General

All trenches or excavations shall be backfilled to the original surface of the ground or such other grades as required or directed. In general the backfilling shall be carried along as speedily as possible in order to avoid open excavations.

6.1.3.2 Bedding and Backfill Materials

Bedding and Backfill material classes referenced within this section shall be defined as follows:

- Class I Angular, 6- to 12.5-millimeters ($\frac{1}{4}$ - to $\frac{1}{2}$ -inch) graded stone such as crushed stone. A No. 11 gravel possessing a minimum 50% mechanical crush count, and meeting the following nominal sizes and percent passing will be considered an equivalent Class I material (100% passing $\frac{1}{2}$ -inch sieve; 75-95% passing a $\frac{3}{8}$ -inch sieve; 10-30% passing No. 4 sieve; and 0-10% passing No. 8 sieve).
- Class II Coarse sands and gravel-sand mixtures with a maximum particle size of 40-millimeters ($1\frac{1}{2}$ -inches), including variously graded sands and gravels containing small percentages of fine, generally granular and non-cohesive, either wet or dry. Soil types GW, GP, SW and SP are included in this class (INDOT Classification for Structural Backfill). These materials will not be accepted as pipe bedding.
- Class III This class is defined as fine sand and clay gravels, including fine sands, sand-clay mixtures and gravel-clay mixtures. Soil types GM, GC, SM and SC (ASTM D2487) are included in this class. These materials will not be accepted as pipe bedding.

6.1.3.3 Backfill of Trench Excavations for Pipes and Conduits

Bedding and Backfill materials samples shall be submitted to the Town prior to start of construction.

6.1.3.4 Bedding

1. Plastic PVC Pipe

Plastic PVC pipe shall be provided with No. 11 crushed stone or approved Class I granular bedding material shovel sliced or otherwise carefully placed and “walked” or hand tamped into place from four (4) to eight (8) inches (based in the diameter of the pipe) below the pipe barrel, to a minimum of twelve (12) inches above the crown of the pipe.

Bedding and initial backfill material shall be hand placed around the haunch and sides of the plastic pipe, to ensure proper compaction filling of all voids. Bedding shall be placed in 6-inch to 8-inch balanced lifts.

2. Ductile Iron Pipe (DI)

Ductile Iron Pipe (DI) shall be provided with Class I granular bedding material. Class I material shall be shovel sliced or otherwise carefully placed and “walked” or hand tamped into place from three (3) to six (6) inches below the pipe barrel, to three (3) inches above the crown of the pipe.

6.1.3.5 Backfill Around Pipe

Do not backfill trenches until the piping system conforms to the contract documents, this manual, special permit conditions, and are approved by the Utility.

Backfill all trenches within State Highway Right-of-Way in accordance with INDOT SS. Backfill trenches in rights-of-way in accordance with the requirements of the AHJ.

Initial backfill material shall be hand placed around the haunch and sides of PVC or DIP pipe to ensure proper compaction filling of all voids. Initial backfill shall be placed in six (6) to eight (8) inch balanced lifts.

Backfill trenches under and within five (5) feet of all paved roads, drives, paved alleys, sidewalks, curb and gutter with full depth granular Class I or Class II material placed in eight (8) inch layers and mechanically compacted to 95% Standard Proctor Density. Prepare upper portion of the trench for surface restoration or pavement replacement.

Backfill trenches at unpaved driveways and alleys with suitable excavated material up to the last twelve (12) inches which shall be the same material as the original surface. Place backfill in eight (8) inch layers and mechanically compact to 95% Standard Proctor Density. Backfill material shall be Class I or II for PVC pipe. Class I, II, or III backfill is acceptable for DI pipe.

Backfill trenches under sidewalks greater than five (5) feet from roadways with suitable excavated material placed in eight (8) inch layers and compacted to 95% Standard Proctor Density. Backfill material shall be Class I or II for PVC pipe. Class I, II, or III backfill is acceptable for DI pipe.

Backfill trenches in areas not requiring granular fill with suitable excavated material compacted to produce an adequate foundation for seeding. The top four (4) inches of backfill shall not contain stones or other objects larger than one (1) inch. Backfill should be mounded above the finished grade to allow for settlement. Place six (6) inches of clean topsoil over the area to be seeded. Area to be restored shall be graded subsequent to settlement and immediately before restoration.

Maintain backfilled trenches in a smooth and uniform condition until paving or seeding operations are completed. Contractor shall refill and restore to the original grade any settlement in the backfill which takes place within the one (1) year warranty period at no additional cost to the Town.

Perform compaction tests at all road crossings and at locations of the trench backfill in accordance with the INDOT SS. The Contractor shall be responsible for payment of all compaction tests.

6.1.4 Installation of Water Mains

6.1.4.1 General

The Contractor shall provide all tools, labor and equipment necessary for the safe and expeditious installation of all water mains, water services, and appurtenances.

Inspect water pipe, valves, hydrants, and appurtenances prior to installation and promptly replace damaged or unsuitable materials with new and unused materials.

6.1.4.2 Installation of Water Mains

Water mains shall be constructed in accordance with the contract documents. Generally, water mains shall be laid uniformly to line and grade. The contractor shall set line and grade for all water main construction based

on the contract documents. DI and PVC pipe water mains shall be laid progressively upgrade with bell upstream in a manner to construct concentric joints with smooth bottom inverts.

Piping systems shall be temporarily plugged in a watertight manner at the end of each day's work, or other interruption of construction, to prevent entry of animals, fluids, or deleterious material.

Bedding material shall be placed along each side of the installed pipe maintain proper alignment. Bedding shall be in accordance with section 6.1.3 of this manual and any permitted conditions.

Tracer wire shall be installed above newly constructed water mains and appurtenances in accordance with the Utility standard details. All new mains must include tracer wire for use in record drawing preparation.

Installed pipe shall not be backfilled without prior inspection by the Utility. Visual line and ownership indicators may be required.

6.1.4.3 Installation of Valves, Valve Boxes, and Structures

Excavations for valves, vaults, meters, hydrants, and other appurtenances shall be kept free of water during construction. Over excavation below the required depth of the structure shall be backfilled in accordance with section 6.1.3 of this manual and the contract documents. Pipe shall be fully bedded, restrained, and supported prior to installation of valves or structures. Install valves per manufacturer specifications. Unless otherwise noted, castings and covers shall be set at finish grade level in accordance with Utility standard details. The Contractor is responsible for adjusting the casting and cover to the satisfaction of the Chandler Utilities.

Remove all debris and excess soil from the structures and boxes after construction and prior to testing and inspection.

6.1.5 Erosion Control

6.1.5.1 General

The Contractor shall be responsible for all temporary and permanent control measures to reduce water pollution, soil erosion, and siltation through the use of berms, dikes, dams, sediment basins, fiber mats, gravel, mulches, grasses, slope drains, and other erosion control devices or methods.

An IDEM Rule 5 permit must be obtained for projects that disturb one (1) acre or more and provided to Chandler Utilities prior to construction commencement. The Contractor shall comply with all requirements of IDEM Rule 5 – Storm Water Run-Off Associated with Construction Activity. The Contractor shall be responsible for notifying all agencies and posting all public notices necessary to comply with Rule 5. The following information shall be posted at the project site: Notice of Intent (NOI) letter and NPDES permit number; the name, address, and phone number of the local contact person; and the location of a copy of the construction plans.

Material handling and storage associated with construction activity shall meet the spill prevention and spill response requirements in Indiana Administrative Code 327 IAC 2-6.1.

All erosion control measures shall be maintained throughout the project and until such time as the disturbed area has been completely stabilized or other provisions have altered the need for these measures. All maintenance shall be provided at the Contractor's expense.

The Utility shall be notified when land disturbing activities have been completed, the entire site has been stabilized and all temporary erosion control measures have been removed. The Developer shall submit a Notice of Termination (NOT) letter to regulating authorities and the Town.

APPENDIX A: STANDARD DETAILS

| <u>Figure</u> | <u>Description</u> |
|----------------------|---|
| 1A | Standard Plan Notes 1 |
| 1B | Standard Plan Notes 2 |
| 2 | Typical Water Main Trench |
| 3 | Fire Hydrant Assembly |
| 4 | Pressure Tapping Detail |
| 5 | ¾ inch to 1 ½ inch Water Service Connection |
| 6 | 2 inch Water Service Connection |
| 7 | Standard Valve Box Detail |
| 8 | Air Relief Assembly |
| 9 | Typical Restraining for Valves and Reducers |
| 10 | Typical Offset Assembly |
| 11 | Restrained Joint Detail |
| 12A | Greater Than 2 Inch Domestic Meter |
| 12B | Greater Than 2 Inch Domestic Meter Notes |
| 13 | Blow-Off Valve Detail |
| 14 | Boring Section and Casing Detail |
| 15 | Location Marker w/ Tracer Wire Terminal Test Points |

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE CHANDLER UTILITIES RULES AND REGULATIONS.
2. CONTRACTOR SHALL PROVIDE DETAILED SHOP DRAWINGS OF ALL MATERIALS AND PRODUCTS TO CHANDLER UTILITIES PRIOR TO AUTHORIZING SHIPMENT TO THE PROJECT SITE.
3. WATER MAIN TO BE INSTALLED THE WITH MINIMUM COVER OF 36 INCHES..
4. MAINTAIN 18' VERTICAL SEPARATION AND 10' HORIZONTAL SEPARATION FROM EXISTING SEWERS, UNLESS OTHERWISE SHOWN ON THE PLANS.
5. CONTRACTOR IS RESPONSIBLE TO OBTAIN AND VERIFY FIELD LOCATIONS OF ALL KNOWN EXISTING BURIED UTILITIES.
6. CONTRACTOR SHALL NOT ALLOW THE USE OF THE PROPOSED WATER MAINS UNTIL ALL CHLORINATION IS COMPLETE AND MAIN IS ACCEPTED BY UTILITY.
7. CONTRACTOR SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL CODES, ORDINANCES, RULES, REGULATIONS, ORDERS, AND OTHER LEGAL REQUIREMENTS OF MUNICIPAL AUTHORITIES WHICH BEAR ON THE PERFORMANCE OF THE WORK.
8. PVC PIPE MAY BE BENT NO MORE THAN 12.3 INCHES OVER A 20" JOINT. USE FITTINGS AS NECESSARY TO PREVENT OVER-DEFLECTION OF PIPE.
9. ALL RESTRAINED JOINTS PER CHANDLER UTILITIES SPECIFICATIONS.
10. ALL FIRE HYDRANTS TO BE LOCATED SO THAT THEY DO NOT INTERFERE WITH THE SIDEWALK. (WHERE APPLICABLE)
11. THE CONTRACTOR IS CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF VARIOUS UTILITY COMPANIES, AND WHERE POSSIBLE MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CONTACT THE APPROPRIATE UTILITY COMPANY AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF ESTABLISH ELEVATIONS AND CLEARANCES WITH PROPOSED IMPROVEMENTS PRIOR TO INITIATING CONSTRUCTION.
INDIANA UNDERGROUND UTILITY LOCATE SERVICE (I.U.P.P.S.)
PHONE: 1-(800)-382-5544
12. ALL SHORT NIPPLES (16" OR LESS) BETWEEN FITTINGS AND VALVES TO BE DUCTILE IRON PIPE.
13. CONTRACTOR SHALL COORDINATE LOCATION OF TAPS, SERVICE TRANSFERS, CORPORATION STOPS, CURB STOPS, VALVES, AND FIRE HYDRANTS WITH CHANDLER UTILITIES.
14. REQUIRED FITTINGS AND APPURTENANCES MAY NOT BE SHOWN ON DRAWINGS. ALL FITTINGS AND APPURTENANCES REQUIRED TO COMPLETE THE PROJECT ARE TO BE INCLUDED IN THE BID PRICE.
15. IT IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO MAINTAIN THE INTEGRITY OF THE METER PIT AND ALL ADJACENT APPURTENANCES ONCE INSTALLATION IS COMPLETE. ANY DAMAGES INCURRED BY THESE DEVICES SHALL BE THE FINANCIAL RESPONSIBILITY OF THE DEVELOPER'S GENERAL CONTRACTOR .
16. EXISTING UTILITY POLES MAY REQUIRE SUPPORTING DURING CONSTRUCTION. CONTRACTOR SHALL COORDINATE WITH UTILITY RESPONSIBLE FOR POLES TO PROVIDE ADEQUATE SUPPORTING DURING CONSTRUCTION.
17. CONTRACTOR SHALL FIELD VERIFY THE DEPTH OF EXISTING WATER MAINS WHERE THEY WILL BE CROSSED BY NEW WATER MAINS. A MINIMUM OF 12 INCHES OF CLEARANCE SHALL BE MAINTAINED BETWEEN NEW AND EXISTING WATER MAINS WHERE THEY CROSS.

TOWN OF CHANDLER

101 CONSTITUTION COURT. CHANDLER, IN 47610

STANDARD PLAN NOTES

Approved: 05/05/2017

Adopted: __/__/__

Figure

Approved By: JSL/ RDC

Scale: N.T.S.

1A

18. CONTRACTOR SHALL BE RESPONSIBLE FOR STAKING RIGHT-OF-WAY BY REGISTERED LAND SURVEYOR.
19. TWENTY FOUR (24) HOURS PRIOR TO STARTING ANY OF THE WORK, THE CONTRACTOR SHALL MAKE ARRANGEMENTS WITH CHANDLER UTILITIES TO PROVIDE INSPECTION FOR THE WORK.
20. CONTRACTOR SHALL SCHEDULE A PRE-CONSTRUCTION MEETING WITH CHANDLER UTILITIES AND THE DESIGN ENGINEER A MINIMUM OF FORTY-EIGHT (48) HOURS PRIOR TO STARTING ANY WORK.
21. CONTRACTOR IS RESPONSIBLE FOR OBTAINING A RULE 5 PERMIT WHERE PROJECT LAND DISTURBANCE EXCEEDS ONE (1) ACRE.
22. CONTRACTOR TO PROTECT AND REPAIR ALL DAMAGED DRAINAGE TILE ENCOUNTERED DURING CONSTRUCTION.
23. CONTRACTOR SHALL HAVE A COPY OF THE CONTRACT DOCUMENTS AND CONSTRUCTION PERMITS ONSITE AT ALL TIMES.
24. WHEN GRADING OPERATION ARE COMPLETE OR SUSPENDED FOR MORE THAN 14 DAYS, PERMANENT GRASS MUST BE ESTABLISHED AT SUFFICIENT DENSITY TO PROVIDE EROSION CONTROL ON SITE. BETWEEN PERMANENT GRASS SEEDING PERIODS, TEMPORARY COVER SHALL BE PROVIDED.
25. ALL FINISHED GRADES IN EXCESS OF 20% SLOPES (5:1) SHALL BE MULCHED AND TACKED AT A RATE OF 100 POUNDS PER 1000 SQUARE FEET WHEN SEEDED.
26. ALL TRENCH BACK FILLS UNDER PAVED AREAS SHALL BE GRANULAR BACK FILL, AND COMPACTED MECHANICALLY. ALL OTHER TRENCH BACK FILLS MAY BE EARTH MATERIAL (FREE OF LARGE CLODS, OR STONES) AND COMPACTED.
27. CONTRACTOR SHALL BE RESPONSIBLE FOR FINAL SITE GRADING, EXCESS SOIL AND SPOIL MATERIAL SHALL BE DISPOSED OF BY THE CONTRACTOR OFF-SITE, AT NO ADDITIONAL COST TO THE OWNER.
28. CONTRACTOR TO REGRADE AREAS AS NECESSARY WITHIN THE CONSTRUCTION LIMITS TO ALLOW PROPER DRAINAGE TO EXISTING AND PROPOSED STORM SEWER STRUCTURES AND DRAINAGE OUTLETS.
29. FINAL GRADES REQUIRE APPROVAL FROM CHANDLER UTILITIES.
30. EXISTING WATER MAIN AND SERVICES SHALL BE PRESERVED AND PROTECTED DURING CONSTRUCTION. SERVICES SHALL REMAIN IN SERVICE UNTIL THE PROPOSED WATER MAIN CONSTRUCTION AND TESTING IS COMPLETE, AT WHICH TIME SERVICES SHALL BE TRANSFERRED. ONCE EXISTING SERVICES ARE TRANSFERRED, EXISTING WATER MAIN MAY BE RETIRED AS APPLICABLE.

UTILITY CONTACTS:

| | | | |
|--|--|---|--|
| CHANDLER UTILITIES 101 CONSTITUTION COURT CHANDLER, IN 47610 (812) 925-6213 | TEXAS GAS TRANSMISSION 7935 INDIANA 56 HAZELTON, INDIANA 47640 (812) 354-8836 | TIME WARNER - NEWBURGH PO BOX 21798 OWENSBORO, KENTUCKY 42301 (270) 685-2991 | AT&T 5858 NORTH COLLEGE AVENUE INDIANAPOLIS, INDIANA 46220 (317) 252-4007 |
| BOONEVILLE / CHANDLER NATURAL GAS 1425 NORTH ROCKPORT ROAD BOONEVILLE, INDIANA 47601 (812) 897-2260 | INSIGHT COMMUNICATIONS 1900 NORTH FARES AVENUE EVANSVILLE, INDIANA 47711 (812) 428-2477 | ZAYO BANDWIDTH 625 EAST 11TH STREET INDIANAPOLIS, INDIANA 46202 (317) 524-5711 | VECTREN GAS 1 NORTH MAIN STREET EVANSVILLE, INDIANA 47702 (812) 491-4607 |

TOWN OF CHANDLER
101 CONSTITUTION COURT. CHANDLER, IN 47610

STANDARD PLAN NOTES

Approved: 05/05/2017


Adopted: __/__/__

Figure

Approved By: JSL/ RDC

Scale: N.T.S.

1B



PAVEMENT REPLACEMENT REQUIREMENTS

| | |
|--------------------------------|--|
| ASPHALT STREETS (RESIDENTIAL) | 660#/SY HMA FOR BASE AND SURFACE |
| ASPHALT STREETS (COLLECTOR) | 980#/SY HMA FOR BASE AND SURFACE |
| CONCRETE STREETS (RESIDENTIAL) | 6" PCCP WITH EXPANSION AND JOINTS TO MATCH EXISTING STREET |
| CONCRETE STREETS (COLLECTOR) | 10" PCCP WITH DOWELS AND EXPANSION AND JOINTS TO MATCH EXISTING STREET |

TOWN OF CHANDLER

101 CONSTITUTION COURT. CHANDLER, IN 47610

TYPICAL WATER MAIN TRENCH

Approved: 05/05/2017


Approved By: JSL/ RDC

Adopted: __/__/__

Scale: N.T.S.

Figure

2



APPROVED HYDRANTS:

- MUELLER
- CLOW
- EAST JORDAN

TOWN OF CHANDLER

101 CONSTITUTION COURT. CHANDLER, IN 47610

FIRE HYDRANT ASSEMBLY

Approved: 05/05/2017


Approved By: JSL/ RDC

Adopted: __/__/__

Scale: N.T.S.

Figure

3



1. WATER MAIN SHALL BE CLEANED BEFORE ATTACHING SLEEVE.
2. SLEEVE AND VALVE SHALL BE PRESSURE TESTED BEFORE MAKING TAP.
3. PRESSURE TEST AND TAP SHALL BE MADE IN THE PRESENCE OF AN AUTHORIZED TOWN REPRESENTATIVE.
4. PROPER TAPPING MACHINE SHALL BE USED TO MAKE TAP.
5. $\frac{3}{4}$ " CRUSHED AGGREGATE SHALL BE PLACED BELOW AND AROUND SLEEVE AND COMPACTED TO 95% OF MAX. DENSITY AS DETERMINED BY AASHTO T-180.
6. TAP SHALL BE MADE NO CLOSER THAN 18" FROM THE NEAREST JOINT.
7. TRENCH TAPPING SLEEVE TO MAIN SHALL BE PLACED

TOWN OF CHANDLER

101 CONSTITUTION COURT. CHANDLER, IN 47610

PRESSURE TAPPING DETAIL

Approved: 05/05/2017


Approved By: JSL/ RDC

Adopted: __/__/__

Scale: N.T.S.

Figure

4



NOTE:

1. USE 1" MATERIAL AND FITTINGS FOR 1" SERVICES.
2. USE 3/4" MATERIAL AND FITTINGS FOR 3/4" SERVICES.
3. SUBSTITUTES FOR ANY MATERIALS SHOWN SHALL BE APPROVED BY THE CITY UTILITIES
4. ALL PIPE AND STRUCTURE ZONES SHALL BE BACKFILLED USING 3/4" MINUS CRUSHED AGG. AND COMPACTED TO 95% MAX. DENS. AS DETERMINED BY AASHTO T-180.
5. METER BOX SHALL BE CENTERED OVER THE COMPLETED METER ASSEMBLY

TOWN OF CHANDLER

101 CONSTITUTION COURT. CHANDLER, IN 47610

3/4" OR 1" WATER SERVICE CONNECTION

Approved: 05/05/2017



Approved By: JSL/ RDC

Adopted: __/__/__

Scale: N.T.S.

Figure

5



TOWN OF CHANDLER

101 CONSTITUTION COURT. CHANDLER, IN 47610

2" WATER SERVICE CONNECTION

Approved: 05/05/2017


Approved By: JSL/ RDC

Adopted: __/__/__

Scale: N.T.S.

Figure

6



TOWN OF CHANDLER

101 CONSTITUTION COURT. CHANDLER, IN 47610

STANDARD VALVE BOX DETAIL

Approved: 05/05/2017


Approved By: JSL/ RDC

Adopted: __/__/__

Scale: N.T.S.

Figure

7



Date: May 05, 2017, 8:29am User: M.Lorenz
 File: S:\112-0057\16DW WR\CAD\Figures\Air Relief Assembly.dwg

TOWN OF CHANDLER

101 CONSTITUTION COURT. CHANDLER, IN 47610

AIR RELIEF ASSEMBLY


Approved: 05/05/2017

Adopted: __/__/__


Figure

Approved By: JSL/ RDC


Scale: N.T.S.




VALVES (NON-DEAD END) 8" AND SMALLER



VALVES (NON-DEAD END) 12" AND LARGER



REDUCERS - LARGER PIPE DIAMETER IS 8" OR SMALLER



REDUCERS - LARGER PIPE DIAMETER IS 12" OR LARGER

TOWN OF CHANDLER

101 CONSTITUTION COURT. CHANDLER, IN 47610

TYPICAL RESTRAINING FOR VALVES & REDUCERS

Approved: 05/05/2017


Adopted: __/__/__

Figure


Approved By: JSL/ RDC

Scale: N.T.S.

9



STREAM CROSSING



UTILITY CROSSING

NOTES:

1. WHERE IT IS NOT POSSIBLE FOR THE WATER LINE TO BE 1.5 FEET ABOVE THE SEWER LINE, OR THE WATER LINE PASSES UNDER THE SEWER LINE, THE EXISTING SEWER LINE SHALL BE EXPOSED FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE CROSSING, AND SHALL BE REPLACED WITH CLASS 50 DUCTILE IRON PIPE AS APPROVED BY THE ENGINEER, AND A LENGTH OF WATER PIPE SHALL CENTERED AT THE CROSSING, OR AS APPROVED BY THE ENGINEER.
2. DUCTILE IRON CLASS 52 PIPE WITH M.J. FITTINGS, ONE FULL PIPE LENGTH CENTERED ON CROSSING

TOWN OF CHANDLER

101 CONSTITUTION COURT. CHANDLER, IN 47610

TYPICAL OFFSET ASSEMBLY

Approved: 05/05/2017

Approved By: JSL/ RDC


Adopted: __/__/__

Scale: N.T.S.

Figure


10

SERRATED TORQUE-LIMITING
SCREWS SUFFICIENT TO HOLD
WORKING AND TEST PRESSURES
(EBAA IRON SERIES 2000 PV FOR
PVC PIPE AND MEGALUG FOR D.I.
PIPE OR APPROVED EQUIVALENT)



PVC OR D.I. PIPE


SUFFICIENT No./DIA. OF
DUCTILE TIE BOLTS OR TIE
RODS TO RESTRAIN WORKING
AND TEST PRESSURES




MECHANICAL JOINT PIPE

RESTRAINED JOINTS ON MECHANICAL JOINT PIPE & FITTINGS

SERRATED TORQUE-LIMITING
SCREWS SUFFICIENT TO HOLD
WORKING AND TEST PRESSURES
(EBAA IRON SERIES 2000 PV FOR
PVC PIPE AND MEGALUG FOR D.I.
PIPE OR APPROVED EQUIVALENT)



SUFFICIENT No./DIA. OF DUCTILE
TIE BOLTS OR TIE RODS TO
RESTRAIN WORKING AND TEST
PRESSURES



SLIP JOINT PIPE

RESTRAINED JOINTS ON SLIP JOINT PIPE

(USING GRIPPING TYPE RETAINERS)

MINIMUM FOOTAGE OF RESTRAINED PIPE FOR VARIOUS
DIAMETERS & DEGREES CAST & DUCTILE IRON ELBOWS

| COVER DIA. MAIN | DEGREE OF ELBOW | | | | | | BRANCH OF TEE | REDUCER (LARGE SIDE ONLY) |
|--------------------|-----------------|-------|-----|-----|------------------------|--------------------|---------------|------------------------------|
| | 11 ¼° | 22 ½° | 45° | 90° | VERTICAL OFFSET 45° | | | |
| | | | | | UPPER BEND (3') | LOWER BEND (3') | | |
| 6" | 2' | 5' | 10' | 25' | 49' | 10' | 9' | 159' |
| 8" | 3' | 6' | 13' | 32' | 63' | 12' | ?' | ?' |
| 10" | 4' | 8' | 16' | 39' | 77' | 15' | 119' | 107' |
| 12" | 5' | 9' | 19' | 47' | 90' | 36' | 163' | N/A |

TOWN OF CHANDLER

101 CONSTITUTION COURT. CHANDLER, IN 47610

RESTRAINED JOINTS DETAIL

Approved: 05/05/2017



Approved By: JSL/ RDC

Adopted: __/__/__

Scale: N.T.S.

Figure

11



TOWN OF CHANDLER

101 CONSTITUTION COURT. CHANDLER, IN 47610

STANDARD FIRE LINE DOUBLE CHECK VALVE GREATER THAN 2" DOMESTIC METER INSTALLATION DETAIL

Approved: 05/05/2017

Adopted: __/__/__

Figure

Approved By: JSL/ RDC

Scale: N.T.S.

12A

NOTES:

1. DEVELOPER SHALL FURNISH & INSTALL VAULT.
2. VAULT CONSTRUCTION MATERIAL SHALL BE 8" X 8" X 8", 4,500 PSI IN ACCORDANCE WITH ASTM C-913.
3. TOP OF VAULT TO BE CONCRETE AT LEAST 4" THICK WITH REINFORCING SUITABLE FOR ANTICIPATED LOADING. WHEN VAULT IS CONSTRUCTED IN PAVED AREAS, PAVEMENT IS TO BE LEVEL WITH TOP OF VAULT, AND THE TOP REINFORCED AS REQUIRED TO SUPPORT TRAFFIC LOADS (I.E. H-20 WHEEL LOADS). WHEN VAULT IS CONSTRUCTED IN GRASS PLOT, TOP OF VAULT SHALL BE 4" ABOVE FINISHED GRADE.
4. ACCESS HATCH IN TOP OF VAULT SHALL BE 30" X 36" ALUMINUM. ACCESS HATCH SHALL HAVE SAME OR GREATER LOADING CAPACITY AS VAULT LID. PIPE HATCH FRAME DRAIN IS VAULT FLOOR OR FLOOR DRAIN IF APPLICABLE.
5. LADDER FOR VAULT INGRESS AND EGRESS SHALL BE PER OSHA REQUIREMENTS. LADDER MATERIAL SHALL BE ALUMINUM OR FIBERGLASS AND INCLUDE BILCO "LADDER-UP" SAFETY DEVICE OR EQUAL.
6. UTILITY AND DEVELOPER RESPONSIBILITIES:
 - 6.1. UTILITY WILL FURNISH AND INSTALL TAPPING SLEEVE, TAPPING VALVE, VALVE BOX, AND DOMESTIC SERVICE FROM TAP ON MAIN TO TAPPING VALVE.
 - 6.2. DEVELOPER SHALL FURNISH AND INSTALL ALL PIPING FROM DISCHARGE SIDE OF TAPPING VALVE, METER PIT, METER, AND ALL INTERIOR PIPING.
7. CONTRACTOR SHALL VERIFY WITH METER MANUFACTURE FOR THE REQUIRED SPACING BETWEEN SPOOL PIECES FOR INSERTION OF METER.
8. VAULT SHALL BE MADE AS WATER TIGHT AS POSSIBLE.
9. VAULT SHALL HAVE A MINIMUM 3" DRAIN TO THE OUTSIDE.
10. VAULT TO BE CLEAN AND FREE OF DEBRIS PRIOR TO CHARGING OF ALL LINES.
11. ALL PIPING IN VAULT SHALL BE SUPPORTED AS NEEDED AND WITH PROPER MATERIAL.

TOWN OF CHANDLER

101 CONSTITUTION COURT. CHANDLER, IN 47610

STANDARD FIRE LINE DOUBLE CHECK VALVE GREATER THAN 2" DOMESTIC METER INSTALLATION DETAIL

Approved: 05/05/2017


Adopted: __/__/__

Figure

Approved By: JSL/ RDC

Scale: N.T.S.

12B



NOTE:
BLOW OFF PIPING AND GATE VALVE SHALL BE SAME SIZE AS WATER MAIN.

Date: May 05, 2017, 8:30am User Name: MLorenz
File: S:\112-0057\160W WR\CAD\Figures\Blow-Off Valve Detail.dwg

TOWN OF CHANDLER

101 CONSTITUTION COURT. CHANDLER, IN 47610

BLOW-OFF VALVE DETAIL

Approved: 05/05/2017

Approved By: JSL/ RDC




Adopted: __/__/__

Scale: N.T.S.


Figure

13

| | | |
|-----------------------|------------------------------------|-----------------------------|
| 6" | 16" | 0.25" |
| 8" | 20" | 0.25" |
| 12" | 24" | 0.375" |
| 16" | 30" | 0.375" |
| 20" | 30" | 0.375" |
| 24" | 36" | 0.375" |
| 30" | 42" | 0.375" |
| 36" | 54" | 0.5" |
| DI CARRIER PIPE | WELDING STEEL CASING PIPE | CASING PIPE THICKNESS |
| PIPING SIZES | | |



ANGLES TO BE CONSTANT AROUND
ENTIRE CIRCUMFERENCE OF THE
PIPE. NUMBER OF SPACERS PER
MANUFACTURER'S SPECIFICATIONS



TOWN OF CHANDLER
101 CONSTITUTION COURT. CHANDLER, IN 47610

BORING SECTION & CASING DETAIL

Approved: 05/05/2017


Adopted: __/__/__

Figure

Approved By: JSL/ RDC

Scale: N.T.S.

14



NOTES:

1. FLEXIBLE UTILITY MARKER WITH TWO TERMINAL TEST ACCESS POINTS FOR TRACER WIRE COLOR BLUE MODEL "TUFFCAT" CTFCO7208U WITH DECALS CW-112 AND TOF-2508 AS MANUFACTURED BY CARSONITE INTERNATIONAL, PH. 1-800-648-7917 (OR EQUAL) TO BE INSTALLED AT 1000 FT. MAXIMUM SPACING, IN FENCE LINES, ADJACENT TO FIRE/FLUSH HYDRANTS, ETC.
2. TRACER WIRE SHALL BE No. 12 AWG USE-2, RHY-2, OR RHH SOLID COPPER WIRE WITH 45 MIL POLYETHYLENE INSULATION AND SUITABLE FOR DIRECT BURIAL INSTALLED LONGITUDINALLY ALONG THE PIPE TRENCH. ALL UNDER GROUND SPLICES IN TRACER WIRE SHALL BE CONNECTED WITH A 3M ELECTRICAL PRODUCT DIVISION No. 054007-09053 DIRECT BURIAL SPLICE KIT.

TOWN OF CHANDLER

101 CONSTITUTION COURT. CHANDLER, IN 47610

LOCATION MARKER W/ TRACER WIRE TERMINAL TEST POINTS

Approved: 05/05/2017

Approved By: JSL/ RDC

Adopted: __/__/__

Scale: N.T.S.

Figure

15